



NOTES AND SPECIFICATIONS:

1. IF CONCRETE WALLS ARE USED, THE PRECAST CONCRETE UNITS SHALL BE MANUFACTURED AND TESTED IN ACCORDANCE WITH ASTM C 478. THE CURING OF THE PRECAST UNITS SHALL CONFORM TO SECTION 207-2.7 OF STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.
2. PRECAST CONCRETE UNITS MAY BE REINFORCED OR UNREINFORCED. REINFORCED SECTIONS SHALL BE REINFORCED IN ACCORDANCE WITH ASTM C 478 AND SHALL HAVE A MINIMUM WALL THICKNESS OF 4".
3. PRECAST CONCRETE UNITS SHALL BE ASSEMBLED USING MORTAR CONFORMING TO SECTION 201-5.1 (CLASS "B") OF THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. FOR LAYING BRICK OR PLASTERING, THE MORTAR SHALL CONFORM TO SECTION 201-5.1 (CLASS "D").

CITY OF LOMITA— PUBLIC WORKS DEPARTMENT

DATE ISSUED	SHALLOW MANHOLE FOR 8" TO 36" PIPE	STANDARD NO.
SEPT 1, 2007		S-105
DATE: AUG 21, 2007	WENDELL E. JOHNSON, CITY ENGINEER CERTIFICATION NO. C 66340	SHEET 1 OF 1